

ADDENDUM#1 **(MARCH 16, 2022)**

Bid NO: 2022-03-06

TOWNSHIP OF PISCATAWAY: “ROADWAY IMPROVEMENTS PLANS JUSTICE STREET”

**PRE-BID Conference / Site Visit Date: N/A-CONTRACTORS ARE STRONGLY
ENCOURAGED TO VISIT THE PROJECT LOCATION.**

Bidder’s Electronic Question Due Date: MARCH 16, 2022 @12NOON

Purchasing@piscatawaynj.org

Bid Submission Due Date: THURSDAY, MARCH 24, 2022 - 2 PM

*Bidders must call the purchasing office at 732-562-2321 to drop off the sealed bid. The
Municipal building is closed to the public due to the Covid-19.*

*Please, make sure your Sealed Bid is dropped off by or before 12NOON 3/24/2022. **Bid
Opening Via ZOOM @2PM:***

Meeting ID: 842 9790 1796
Passcode: 613109

QUESTION

ANSWERS

following questions regarding the Justice Street Project Out to Bid:

- There are several inlets that read as “Reconstruct” (A-1 is an example) however there is no “Reconstruct Type __, Inlet” pay item. How are we getting paid for this scope of work? **Reconstructed inlets shall be paid for under the appropriate “Inlet, Type __” pay item. The term “Reconstruction” notes that there is an existing inlet in the approximate location and that there may be existing connections that need to be maintained.**
- Please confirm that the Type B Inlets that are to be installed with driveway access plates (B-6 is an example) will be paid under the Type B inlet Item, or will a separate pay item be added for the inlets with driveway plates? **No separate pay item will be added for inlets with driveway backplates, they will be paid under the Type B inlet item.**
- Please confirm that both Type Double B Inlets are the “Detention Basin Inlets” and separate pay items are not necessary. **Inlets A-5 and C-9 shall be paid for under the “Type Double B” pay item. Specific details are provided for these structures on Sheet 28 – “Construction Details – 5”**

- The plans propose that Inlet C-5 be converted from a Type B Inlet to a Type E inlet, how are we getting paid for this work? **Based on a review of the proposed quantities, it appears that this work was included under the “Inlet, Type B” pay item.**
- Are trash racks or weirs required to be added at the end of the Headwalls or just the Flared End Sections? **Check valves are required at the end of the headwalls at the downstream most portion of the project. No trashracks or weirs were called for in the plans or specifications.**
- Which manhole casting does the township want? The detail references both a 1202B and a 1203 as well as a watertight casting, does the township want any markings stamped on the cover? **Manhole castings shall be Campbell pattern 1202B with watertight Flow Seal gasket.**
- Do storm sewer trenches need to be paved at the end of each working day? **There is no requirement to pave the trenches, but no trench shall be left open overnight. Access shall be maintained on a daily basis through adequate backfill, plating, or paving.**